

5877 Pine Ave, Ste. 210 Chino Hills, CA. 91709 Phn: (909) 606-7622

Office of Statewide Health Planning and Development PREAPPROVAL OF MANUFACTURER'S CERTIFICATION OPM-0164-13

THIS PREAPPROVAL CONFORMS TO THE 2013 CALIFORNIA BUILDING CODE

MANUFACTURER: GCX CORPORATION

EQUIPMENT NAME: GCX VHC W/ HORIZONTAL RAILS

Sheet: 1 of 6 Date: 12/16/14

GENERAL NOTES

- 1. THIS OSHPD PREAPPROVAL OF MANUFACTURER'S CERTIFICATION (OPM) IS BASED ON THE 2013 CBC. THE DEMANDS (DESIGN FORCES) FOR USE WITH THIS OPM SHALL BE BASED ON THE 2013 CBC
- 2. THIS DOCUMENT MAY ONLY BE USED WITH THE EXPRESS WRITTEN CONSENT OF THE MANUFACTURER LISTED ABOVE FOR THE SPECIFIC PROJECT SITE AND INSTALLATION LOCATION. THIS DOCUMENT IS INVALID WITHOUT SUCH CONSENT.
- 3. THIS PREAPPROVAL CONFORMS TO THE 2013 CALIFORNIA BUILDING CODE.
- 4. FORCES PER ASCE 7-10 SECTION 13.3.1, EQUATIONS 13.3-1, 13.3-2 & 13.3-3, WHERE SDS = 2.00, $a_p = 2.5$, $b_p = 1.5$, $c_p = 2.5$, $c_$
- 5. THE DETAILS IN THIS PREAPPROVAL MAY BE USED AT ANY LOCATION IN THE STATE OF CALIFORNIA, WHERE SDS IS NOT GREATER THAN 2.00.

 BY: William Staehlin
- 6. ALL DESIGN FORCES SHOWN ON THE DRAWINGS ARE FACTORED LOADS THAT SHALL BE USED FOR STRENGTH DESIGN.
- 7. SHEET METAL SCREWS SHALL BE TEKS SCREWS BY ITW BUILDEX (ICC ESR-1976).
- 8. THIS PREAPPROVAL COVERS ONLY THE SUPPORTS AND ATTACHMENTS OF THE EQUIPMENT TO THE STRUCTURE.
- 9. RESPONSIBILITIES OF THE STRUCTURAL ENGINEER OF RECORD OF THE BUILDING
 - A. PROVIDE SUPPORTING STRUCTURE REQUIRED TO SUPPORT WEIGHTS AND FORCES SHOWN, IN ADDITION TO ALL OTHER LOADS.
 - B. VERIFY THAT THE INSTALLATION IS IN CONFORMANCE WITH THE 2013 CBC AND WITH THE DETAILS SHOWN IN THIS PREAPPROVAL. VERIFY THAT THE ACTUAL EQUIPMENT'S WEIGHT, CG LOCATION, ANCHOR LOCATIONS, ANCHOR DETAILS AND THE MATERIAL AND GAGE OF THE UNIT WHERE ATTACHMENTS ARE MADE AGREE WITH THE INFORMATION SHOWN ON THE PREAPPROVAL DOCUMENTS.
 - C. VERIFY THAT THE COMBINATION OF SDS & z/h RESULT IN SEISMIC FORCES (Eh , Ev) THAT ARE NOT GREATER THAN THE VALUES ON THE DETAILS.
 - D. DESIGN BACKING BARS, STUDS, ETC. WHICH THE UNITS ARE ATTACHED TO AS NOTED ON THE DRAWINGS.



EQUIPMENT ANCHORAGE & SEISMIC ENGINEERING

DES. J. ROBERSON

www.EquipmentAnchorage.com

METAL STUD FRAMING REFER TO SHEET 4 & 6 OF 6

FOR WOOD STUD FRAMING

GCX CORPORATION

11-1441 JOB NO.


GCX VHC W/ HORIZONTAL RAILS

12/16/14 DATE

SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

WALL MOUNTED



NOTES:

 FORCES ARE DETERMINED PER 2013 CALIFORNIA BUILDING CODE AND ASCE 7-10 STRENGTH DESIGN IS USED. (SDS = 2.00, Ap = 2.5, Ip = 1.5, Rp = 2.5, Z/h < 1)

> HORIZONTAL FORCE (En) = 3.60 Wp VERTICAL FORCE (Ev) = 0.40 Wp

- 2. CENTER OF GRAVITY (C.G.) AND WEIGHT ARE THE GOVERNING PARAMETERS FOR DESIGN. THIS PREAPPROVAL ENCOMPASS ALL WEIGHTS UP TO THE MAXIMUM WEIGHT SHOWN.
- 3. STRUCTURAL ENGINEER OF RECORD FOR THE BUILDING SHALL PROVIDE SUPPORT STRUCTURE DESIGNED TO SUPPORT WEIGHTS AND FORCES SHOWN IN COMBINATION WITH ALL OTHER LOADS THAT MAY BE PRESENT.



EASE

EQUIPMENT ANCHORAGE & SEISMIC ENGINEERING

DES. J. ROBERSON

www.EquipmentAnchorage.com

GCX CORPORATION

јов no. **11-1441**

3

GCX VHC W/ HORIZONTAL RAILS


DATE 12/16/14

OF 6 SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

48" TRACK

WALL MOUNTED



Tu = 379 LB/SCREW (MAX) Vu = 95 LB/SCREW (MAX)



EASE

EQUIPMENT ANCHORAGE & SEISMIC ENGINEERING

www.EquipmentAnchorage.com

GCX CORPORATION


JOB NO. 11-1441

4

GCX VHC W/ HORIZONTAL RAILS

DATE 12/16/14

- 6 SHEETS



ELEVATION AT WALL PLATE (RAILS TO WALL)

 $T_u = 134 LB/SCREW (MAX)$ $V_u = 98 LB/SCREW (MAX)$



EASE

EQUIPMENT ANCHORAGE & SEISMIC ENGINEERING

www.EquipmentAnchorage.com

GCX CORPORATION

DES. J. ROBERSON
JOB NO. 11-1441

5

GCX VHC W/ HORIZONTAL RAILS


DATE 12/16/14

OF 6 SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

36" TRACK

WALL MOUNTED



 $T_u = 385 LB/SCREW (MAX)$ $V_u = 95 LB/SCREW (MAX)$



EQUIPMENT ANCHORAGE & SEISMIC ENGINEERING

www.EquipmentAnchorage.com

GCX CORPORATION


DES. J. ROBERSON 11-1441

GCX VHC W/ HORIZONTAL RAILS

12/16/14 DATE

JOB NO.

SHEETS



Tu = 141 LB/SCREW (MAX) Vu = 98 LB/SCREW (MAX)

(RAILS TO WALL)

